ONTENTS

VICINITY MAP, SOW, TTC NOTES, LEGEND,
TYPICAL, TTC DESIGN SHEET (PHASE 1)

2-3

TTC DESIGN SHEETS (PHASE 2)

# SAMPLE CLIENT SAMPLE PROJECT

SAMPLE STREET A & SAMPLE STREET B, SAMPLE CITY, CA

#### TTC NOTES


- INDIVIDUALS WHO ARE KNOWLEDGEABLE IN THE PRINCIPLES OF PROPER TTC SHOULD BE ASSIGNED RESPONSIBILITY FOR SAFETY IN TTC ZONES, TO CHECK THAT ALL TTC DEVICES OF THE PROJECT ARE REASONABLY CONSISTENT WITH THE TTC PLAN AND ARE EFFECTIVE IN PROVIDING REASONABLY SAFE CONDITIONS FOR MOTORISTS, BYCYCLISTS, PEDESTRIANS, AND WORKERS.

- AS WORK PROGRESSES TEMPORARY TRAFFIC CONTROLS AND/OR WORKING CONDITIONS SHOULD BE MODIFIED IN ORDER TO PROVIDE REASONABLY SAFE AND EFFICIENT ROAD USER MOVEMENT AND TO PROVIDE WORKER SAFETY. THE INDIVIDUAL RESPONSIBLE FOR TTC SHOULD HAVE THE AUTHORITY TO HALT WORK UNTIL APPLICABLE OR REMEDIAL SAFETY MEASURES ARE TAKEN.

- ALL TEMPORARY TRAFFIC CONTROL DEVICES SHALL BE REMOVED AS SOON AS IS PRACTICAL.
- AUDIBLE INFORMATION DEVICES ARE TO BE USED TO ASSIST PEDESTRIANS WITH VISUAL DISABILITIES WHERE NEEDED.
- ALL DRIVEWAYS ARE TO REMAIN OPEN AT ALL TIMES.
- CONTRACTOR TO CONTACT LOCAL TRANSIT AGENCY WHEN REQUIRED WORK IMPACTS PUBLIC TRANSPORTATION.
- -CONTRACTOR TO PLACE TEMPORARY NO PARKING SIGNS 48HRS IN ADVANCE OF CLOSING ANY PARKING LANES.
- ALL TTC WILL BE COMPLIANT WITH THE MOST RECENT CALIFORNIA MUTCD AND/OR WATCHBOOK PER LOCAL JURISDICTIONAL REQUIREMENTS

#### PEDESTRIAN NOTES:

- A DEDICATED INDIVIDUAL WILL BE ASSIGNED THE RESPONSIBILITY OF ESCORTING PEDESTRIANS THROUGH THE WORK AREA IN ACCORDANCE WITH THREE MAJOR CONSIDERATIONS:
- . PEDESTRIANS SHOULD NOT BE LED INTO DIRECT CONFLICT WITH WORK SITE VEHICLES, EQUIPMENT, OR OPERATIONS
- 2. PEDESTRIANS SHOULD NOT BE LED INTO DIRECT CONFLICT WITH MAINLINE TRAFFIC MOVING THROUGH OR AROUND THE WORK SITE.
- 3. PEDESTRIANS SHOULD BE PROVIDED WITH A REASONABLE, SAFE, CONVENIENT, AND ACCESSIBLE PATH THAT REPLICATES AS NEARLY AS PRACTICAL THE MOST DESIRABLE CHARACTERISTICS OF THE EXISTING SIDEWALK OR 5' MINIMUM FOOTPATH.



## PHASE 1 (TRENCH / VAULT PLACEMENT)

NOTES:

WORK HOURS 9:00 A.M. - 3:30 P.M. MONDAY - FRIDAY
 DRIVEWAY ACCESS TO BE MAINTAINED AT ALL TIMES

- ALL TEMPORARY TRAFFIC CONTROL DEVICES TO BE REMOVED AT THE END OF EACH SHIFT

 WORK AREA

W 68th St

W 70th St

W 73rd St

W 75th St

W 75th St

W 75th St

O 2020 Microsoft Corporation Q 2020 HERE

SCOPE OF WORK

TEMPORARY TRAFFIC CONTROL DEVICE AND SIGN PLACEMENT IN SAMPLE CITY RIGHT OF WAY FOR 798' UNDERGROUND CONSTRUCTION

### LOGDNI

TRAFFIC SIGNAL

FLASHING ARROW BOAF

FLASHING ARROW BOARD I TYPE III BARRICADE / WITH SIGN

EXISTING TURN-ONLY LANE

FLAGGER

→ EXISTING NO-TURN LANE⇒ TRAFFIC FLOW DIRECTION

TRAFFIC SIGN


DRIVEWAY

WORK ZONE

TRAFFIC CONE

χ χ TYPE II BARRICADE / WITH SIGN

#### PEDESTRIAN DETOUR PLAN



TYPICAL APPLICATION 28

Note: See Tables 6H-2 and 6H-3 for the meaning of the symbols and/or letter codes used in this figure.

Chapter 6H - Typical Applications

# REVISION NOTES

DAIL	DESCRIPTION	IINIIIAES
-	<del></del>	
-		-
-		-

PREPARED BY:

Telecom Solutions, LLC

2001 THIRD ST #H, RIVERSIDE, CA 92507
(626) 320 - 0996 | peterm@ospros.net

TRAFFIC CONTROL

SAMPLE CLIENT

SAMPLE CLIENT ADDRESS
SAMPLE CITY, CA

DRAWN ERS

DESIGN ERS

CHECKED OSPRO

DATE 03/09/2020

SAMPLE PROJECT
SAMPLE STREET A & SAMPLE STREET B
SAMPLE CITY, CA

1 OF
3

PLOTTED: 11/13/2020

